


Main structure is made fro special profile. After galvanization, marine paint is coated to meet the sea transportaion requirement. That makes the lifetime up to 30 years even in humid areas.

Forklift pockets are designed in bottom frame for easy moving.

Four container corners ensure cabin can be locked with shipping container during sea-transportaion.



Insulation of wall, roof and floor is the Neopor EPS, which is developed by BASF Germany.



# INSTALLATION

Patented design, 90% prefabricated in the factory, including prefixed windows and doors into the wall panel, ceiling and floor decoration, electrical system and so on. It only takes one day for three workers to complete one cabin (15 Sq. meters).


Joint: the standard cabin is completely modular design, can be connected in longitudinal and transverse direction for large open interior space. cabins can be stacked and connected by professional container lockset. The strength can meet the requirements of structural calculations.



Besides the 26 basic components for each cabin, we can also provide platform, railing and staircase, which are designed to fix on the cabin easily.


# INSTALLATION

**安装步骤 1 (基本组件尺寸)**  
将基本组件按照尺寸拼装成标准尺寸  
Installation step 01 (The integrated size of Sub-part)  
The integrated size of Sub-part is standard.




4个基本组件拼装成一个标准尺寸  
Four beams are joined into a standard size  
3个基本组件拼装成一个标准尺寸  
Three beams are joined into a standard size

**安装步骤 2 (打开侧门)**  
打开侧门时，按照 (1) 所示方法进行安装。将侧门放入侧门框内，并用专业锁扣固定。侧门框与侧门框之间的缝隙，应使用密封胶填充。  
Installation step 02 (Open the side door)  
Open the side door, using the method shown in Fig. 1. The side door is put into the side door frame and fixed with professional lockset. The gap between the side door frame and the side door frame should be filled with sealant.




**安装步骤 3 (安装侧门)**  
将侧门 (1) 按照图示方法，用专业锁扣 (10) 固定侧门。侧门框与侧门框之间的缝隙，应使用密封胶填充。  
Installation step 03 (Installation of side door)  
After open door (1) are adjusted vertically, using the professional lock (10) to fix the side door. The gap between the side door frame and the side door frame should be filled with sealant.




**安装步骤 4 (安装侧门)**  
将侧门 (1) 按照图示方法，用专业锁扣 (14) 固定侧门。侧门框与侧门框之间的缝隙，应使用密封胶填充。  
Installation step 04 (Installation of side door)  
After the installation of short side wall panel, the installation of drainage pipe (14) should be started. And the installation method and sequence are shown in Fig. 14.




**安装步骤 5 (安装侧门)**  
将侧门 (1) 按照图示方法，用专业锁扣 (10) 固定侧门。侧门框与侧门框之间的缝隙，应使用密封胶填充。  
Installation step 05 (Installation of side door)  
After the side door (1) is put into the side door frame, the side door (1) is fixed with professional lock (10). The gap between the side door frame and the side door frame should be filled with sealant.



**安装步骤 6 (安装侧门)**  
将侧门 (1) 按照图示方法，用专业锁扣 (10) 固定侧门。侧门框与侧门框之间的缝隙，应使用密封胶填充。  
Installation step 06 (Installation of side door)  
Install the side door (1) at the bottom (10), and fix it with professional lock (10). The gap between the side door frame and the side door frame should be filled with sealant.



**安装步骤 7 (安装侧门)**  
将侧门 (1) 按照图示方法，用专业锁扣 (10) 固定侧门。侧门框与侧门框之间的缝隙，应使用密封胶填充。  
Installation step 07 (Installation of side door)  
Install the side door (1) at the bottom (10), and fix it with professional lock (10). The gap between the side door frame and the side door frame should be filled with sealant.



**安装步骤 8 (安装侧门)**  
将侧门 (1) 按照图示方法，用专业锁扣 (10) 固定侧门。侧门框与侧门框之间的缝隙，应使用密封胶填充。  
Installation step 08 (Installation of side door)  
Install the side door (1) at the bottom (10), and fix it with professional lock (10). The gap between the side door frame and the side door frame should be filled with sealant.






# INSTALLATION


## 安装步骤 9 (固定墙体与立柱)

用电动钻在立柱 (8) 的底部每隔 1m/4.0m 处, 90°/4.0m 处钻孔 (20)。  
将墙体与立柱 (8) 固定。  
Installation step 9: [Fixed wall panels and columns]  
Drill / 4.0mm holes on the bottom of panel of corner post (8) with electric drill and fix the wall panel and corner post (8) with / 4.0mm self tapping bolt (20).




## 安装步骤 11 (安装 PVC 踢脚线)

安装 PVC 踢脚线 (12), 先用电钻在踢脚线底部板上打一个 M4.2mm 的孔, 再用 M4.2 的螺钉 (21) 将踢脚线固定在墙体上。每隔 300mm 固定一个。  
Installation step 11: [Installation PVC Floor Skirting]  
About the installation of PVC floor skirting (12), drill a M4.2mm hole on the floor skirting and wall panels with electric drill, then fix the floor skirting and wall panel with M4.2 self tapping bolt (21). And do this in every 300mm interval.




## 安装步骤 13 (安装门框立柱)

安装门框立柱 (17)。  
Installation step 13: [Installation of door frame]  
Installation of door frame (17)




## 安装步骤 14 (安装门框立柱)

安装门框立柱 (17) 和 10A 型门框立柱 (25), 10A 型门框立柱 (25)。  
Installation step 14: [Installation of door frame and wall]  
Installation of wall (25) and 10A ordinary 3-hole socket (25), 10A AC 3-hole socket (25)




## 安装步骤 15 (连接墙体)

将墙体与立柱 (11) 之间的墙体。  
Installation step 15: [Connecting wall]  
Connect the electric wire between wall panel and corner post (11).




## 安装步骤 12 (安装 PVC 踢脚线)

安装 PVC 踢脚线 (10), 先用电钻在踢脚线底部板上打一个 M4.2mm 的孔, 再用 M4.2 的螺钉 (21) 将踢脚线固定在墙体上。每隔 300mm 固定一个。  
Installation step 12: [Installation PVC floor skirting]  
Install the PVC floor skirting (10), then install the PVC floor skirting (11). And the result is same with the PVC floor skirting (12). Then the skirting angle (27) should be changed in the groove of PVC column skirting (10).




## 安装步骤 14 (安装门框立柱)

安装门框立柱 (17)。  
Installation step 14: [Installation of door frame]  
Installation of door frame (17)



## 安装步骤 16 (安装门框立柱)

安装门框立柱 (17)。  
Installation step 16: [Installation of door frame]  
Installation of door frame (17)



# INSTALLATION


## 安装步骤 17 (打胶)

在立柱 (8) 的底部每隔 1m/4.0m 处, 90°/4.0m 处钻孔 (20)。  
Installation step 17: [Glue]  
The weather-proof glue should be applied in the periphery of vertical post (8), as shown in the first line of the Fig.



## 安装步骤 18 (安装门框立柱)

安装门框立柱 (17) 和 10A 型门框立柱 (25), 10A 型门框立柱 (25)。  
Installation step 18: [Installation of door frame]  
Connect the electric wire between wall panel and corner post (11).




## 安装步骤 18 (安装门框立柱)

在立柱 (8) 的底部每隔 1m/4.0m 处, 90°/4.0m 处钻孔 (20)。  
Installation step 18: [Installation of door frame]  
After the installation of door frame (or two frames) into each corner, apply the weather-proof glue. During the applying, the distance of two corners is 1m. Then apply the weather-proof glue (8) into the applying joint, and apply the glue (8) into the joint of the corner post (8) of the two corners' corner. Tighten M20 high-strength bolt (20) to press the rubber seal strip (8) to reach the waterproof effect.



## 安装步骤 19 (安装门框立柱)

安装门框立柱 (17) 和 10A 型门框立柱 (25), 10A 型门框立柱 (25)。  
Installation step 19: [Installation of door frame]  
Installation sequence of internal splicing joint: Molding Pile of Column (1-2), Molding Pile of Floor (1-2), Molding Pile of Floor (1-2).



True blue



# TRANSPORTATION



The module is designed for easy moving and lifting.

- a. The standard sizes: Length 6055mm, width 2435mm, easy for land transportation.
- b. Flat-packed design, 4 individual units could be packed as big as a 20' ISO shipping container which could be transported directly.
- c. The corners can work as the lifting points.
- d. There are forklift-pockets in the base frame for east moving.

*True blue*

# STANDARD CABIN HOUSE

Basic cabin generally used for temporary or permanent office.

As a boss or facility manager, what is your solution if you need to provide a safe and comfortable office space in a short time?

3,000 square meters ex-stocks (200 sets of basic cabins).

The new office can be designed based on the land shape. With the standard 15m<sup>2</sup> cabin, the combination can utilize the land furthest.

The new office can be designed based on the land shape. With the standard 15m<sup>2</sup> cabin, the combination can utilize the land furthest.

If the building is temporary, the new office could be located on the precast concrete foundation, there is no damage to the original turf, which will be easy recovered after removal.





## ENGINEERING CASE BASIC CABIN-SCHOOL



**Project Name:** Aruba  
**Time:** 2015.3  
**Location:** Aruba.Using  
**Floor Area:** 960 sq.m

This project is located in Aruba.Using our modular house as a private school. This project was made by 64 units of 20ft flapacked container to combine, then finished 16 classrooms. Aruba was the colony of Netherlands before, so the electrical system need to meet the Netherlandish standard. We helped the students and provided the space in the very short time. Just two weeks, a 960 sqm private school was finished installation.

## ENGINEERING CASE BASIC CABIN-SCHOOL



**Project Name:** Langfang School  
**Time:** 2015. 2  
**Location:** Langfang, Hebei, China  
**Floor Area:** 1800 sq.m

Depending on the advantages as high workshop prefaabrication extent of modularized box type housing and quick installation at site, etc. The manufacturing installation and acceptance of 120 sets of modularized teaching rooms were completed by only 20s days, so that they can be timely put into use for children in case of school open.





## ENGINEERING CASE BASIC CABIN-HOSPITAL



**Project Name:** Children Rehabilitation Center  
**Time:** 2014. 3  
**Location:** Beijing Children Hospital  
**Floor Area:** 933 sq.m

It is only takes 15 days to erect this 3-storey, 1000m<sup>2</sup> building. In an operating hospital, modular building concept minimized the trouble of daily working caused by construction.



## ENGINEERING CASE BASIC CABIN-SCHOOL



**Project Name:** Guizhou Elementary School  
**Time:** 2015  
**Location:** Qianxi County, Guizhou Province China  
**Floor Area:** 360 sq.m

Shaba Elementary School of Qianxi County, Guizhou is located in Huaxi Village of Qianxi County with sea level of nearly 1000m, it is remotely located with inconvenient traffic condition. Most students in Shaba Elementary School are leftover children, and going to school by climbing mountains and ridges has become the ordinary living of them. The travel between school and their home is an extremely hard work, thus the comfortable and tidy student dormitory shall resolve the problem.



## ENGINEERING CASE BASIC CABIN-HOSPITAL

**Project Name:** Xuanwu Hospital  
**Time:** 2013  
**Location:** Beijing, China  
**Floor Area:** 300+135 sq.m



Modular cabins are combined and stacked to a quadrangle courtyard. The roof veranda is a nice place to enjoy leisure time.

**Project Name:** Cancer Hospital  
**Time:** 2014.6  
**Location:** Beijing, China  
**Floor Area:** 320 sq.m



Standard and Non-standard cabins are combined to achieve a complex including office, storage and equipment room.

## ENGINEERING CASE BASIC CABIN-RESIDENTIAL HOUSE



**Project Name:** Site Office in PNG  
**Time:** 2013  
**Location:** Papua New Guinea

Fresh air bright sunlight will be brought into room through french windows. Steel modular cabin matched with local wooden platform and staircase, it makes the building close to nature.





## ENGINEERING CASE BASIC CABIN-OFFICE SPACE

Temporary office for Saeron Automotive. 30 units are combined to a double story office and big canteen.



**Project Name:** Saeron Automotive  
**Time:** 2013.3  
**Location:** Beijing, China  
**Floor Area:** 450 sq.m



## ENGINEERING CASE BASIC CABIN-EXHIBITION



**Project Name:** Forestry Association caravan forest popular science hut  
**Time:** 2015  
**Location:** Beijing, China

One basic cabin wall can provide 45m<sup>2</sup> as advertisement area. Not exceed transport limitation in height and width, our cabin is suitable for shortterm advertisement. The catalogues and furniture can be store in the cabin during nighttime.



## ENGINEERING CASE BASIC CABIN-OFFICE

The foreign trade office is a typical case of application of modularized box type housing in the office field. The UK designer Michael designed it and directed the installation.

The designer adopted glass curtain wall at the front wall, and organically combined the factors of architectural, building function, building energy conservation and building structure together.

Five 2.4m X 6m box houses are spliced into two-story building. The floor area is 50m<sup>2</sup>, and the erection is completed within 15 days. Interior design comprehensively presents the simplism, including white office desk, chair, black square bookcase, ordinary light color timber floor without disorder feeling.



## ENGINEERING CASE BASIC CABIN-COTTAGE



This resort project is located in an island named Ubin, at a distance of 56 kilometers from Singapore. If in traditional construction methods, it is necessary to large-scale transportation construction equipment and materials on the island, construction time and labor costs will be greatly increased.

The project finally adopted the concept of modular housing, in domestic custom folding box type housings, in Singapore, the island workshop to complete the assembly, shipping to the island, after stacking, adding slop roof and exterior wall finishes. In a short span of 3 months, two 45 storey villa completed the construction.



The project is located in a sea island named Sabah, Malaysia. All parts are manufactured in domestic workshop, after shipped to this island, they finished the installation fast. It is very convenient and quick.

The whole construction is cozy and lively. Inside set bedroom and bathroom, it is appropriate for 2-4 persons for vacation.



## ENGINEERING CASE BASIC CABIN-HOSPITAL



**Project Name:** Xuanwu Hospital Temporary Office  
**Time:** 2013  
**Location:** Beijing, China  
**Floor Area:** 300 sq.m

## ENGINEERING CASE BASIC CABIN-HILLTOP VILLAGE



According to residential habit and residential environment of local people, we can conduct professional customization design, to fuse the building into local cultural environment.

**Project Name:** Villa of Papua New Guinea  
**Time:** 2013  
**Location:** Papua New Guinea



**Project Name:** Dubai seaside restaurant  
**Time:** 2015  
**Location:** Dubai  
**Floor Area:** 330 sq.m





## ENGINEERING CASE BASIC CABIN-SAMPLE HOUSE



- ① installation work day one
- ② installation work day two
- ③ installation work day three
- ④ installation work day four
- ⑤ installation work day five

OCCINE Panel



OCCINE panel is a kind of wall panel. The outer surface is colored steel plate coated by stone like plastering that pre-applied in our factory. Inner surface are pre-painted with interior emulsion paint.

## ENGINEERING CASE BASIC CABIN-SAMPLE HOUSE



Interior decoration work was completed in 7 days. Emulsion painting is used for living area. Wallpaper is used for bedroom. And ceramic tiles are used for bathroom partially. The living room ceiling is decorated with teakwood.

## Residential House





## ENGINEERING CASE BASIC CABIN-SHOP

Yansha Jiku project was made by 24 units of our modular container houses. The roof is filled with glass fiber cotton, a kind of waterproof material. The wall was made by tempered glass so that the people will not feel cold even in cold winter.

In domestic market, more and more people start to use box type housing as commercial store. Multiple shapes can be spliced at any smooth ground. Furthermore it has the advantages as quick and convenient installation, short construction time, removal at any moment, repeated dismantling.

**Project Name:** Yansha Jiku  
**Time:** 2014  
**Location:** Beijing, China



## ENGINEERING CASE BASIC CABIN-COFFEE SHOP



The coffee housing is located in Beijing with 200m2 building area, it is composed of 8 modula box type housing. All installation including interior and exterior decoration are completed within 18 days, two sides wall bodies adopt external hanging panel and it is fashionable and simple, the front wall decorated with hollow glass so that the sunshine can comprehensively fall into every corner in the house, and the whole building is softly fused with the nature.

**Project Name:** Coffee shop  
**Time:** 2015  
**Location:** Beijing, China





## ENGINEERING CASE BASIC CABIN-SHOP

Customer-designed caravan hut is made for Norway client. The front wall of hut is made from full-high glass leading to the outdoor platform. The back wall opened to caravan. The hut is directly connected with the caravan and worked as living room.

**Project Name:** Seaside Caravan Hut  
**Time:** 2012 till now  
**Location:** Norway



## ENGINEERING CASE



## ENGINEERING CASE





# ENGINEERING CASE



# ENGINEERING CASE



# ENGINEERING CASE



# ENGINEERING CASE





## ENGINEERING CASE



## ENGINEERING CASE



## ENGINEERING CASE



## ENGINEERING CASE





## ENGINEERING CASE



## ENGINEERING CASE



## ENGINEERING CASE



## ENGINEERING CASE





# ENGINEERING CASE



# ENGINEERING CASE

